CA724/2





Pre Assembled Shorting Links

Internal Shorting Link Assemblies consist of a Current Bar shorting Sleeves and Screws. They install easily into the centre of the Terminal Block and connect to the current bar. They are available as standard 2, 3, 4 and 10 pole assemblies and are ready for immediate installation.

| PRODUCT SPECIFICATION | |
|-----------------------|--------|
| Rated Current | 57 A |
| Torque | 0.5 Nm |

| ORDERING INFORMATION | | | |
|----------------------|---|-----------|--|
| CAT. NO. | DESCRIPTION | STD. PACK | |
| CA724/2 | Pre Assembled Shorting Link assemblies with 2 poles | 100 | |
| CA724/3 | Pre Assembled Shorting Links assemblies with 3 poles | 50 | |
| CA724/4 | Pre assembled Shorting Link assemblies with 4 poles | 50 | |
| CA724/10 | Pre Assembled Shorting Links assemblies with 10 poles | 100 | |
| CA724/9 | Pre Assembled Shorting Links assemblies with 9 poles | 100 | |

| SUITABLE FOR | | |
|--------------|--|--|
| CTS10UV0 | 10 sq. mm Feed Through Terminal Blocks | |
| CTS10U | 10 sq. mm Standard Feed Through Terminal Blocks | |
| CTS10 | 10 sq.mm Standard Feed Through Terminal Blocks. | |