CA627/2





## Pre Assembled Shorting Links

Internal Shorting Link Assemblies consist of a Current Bar shorting Sleeves and Screws. They install easily into the center of the Terminal Block and connect to the current bar. They are available as standard 2, 3, 4, or 10 pole assemblies and are ready for immediate installation.

PRODUCT SPECIFICATION		
Torque	0.4 Nr	n

ORDERING INFORMATION			
CAT. NO.	DESCRIPTION	STD. PACK	
CA627/2	Preassembled Internal Shorting Link Assemblies with 2 poles	100	
CA627/3	Preassembled Internal Shorting Link Assemblies with 3 poles	100	
CA627/4	Preassembled Internal Shorting Link Assemblies with 4 poles	100	
CA627/10	Preassembled Internal Shorting Link Assemblies with 4 poles	10	

SUITABLE FOR		
CTLG2.5	Three Level + Ground Feed through Terminal block	
CDLG2.5	Two Level + Ground Feed through Terminal block	