

CA721/2



**connectwell**  
THE RIGHT CONNECTION

### Pre Assembled Shorting Links

Internal Shorting Link Assemblies consist of a Current Bar shorting Sleeves and Screws. They install easily into the center of the Terminal Block and connect to the current bar. They are available as standard 2, 3, 4, 10 or 100 pole assemblies and are ready for immediate installation.

#### PRODUCT SPECIFICATION

Rated Current	24 A
Torque	0.4 Nm

#### ORDERING INFORMATION

CAT. NO.	DESCRIPTION	STD. PACK
CA721/2	Preassembled Internal Short Link assemblies with 2 poles	100
CA721/3	Preassembled Internal Short Link assemblies with 3 poles	100
CA721/4	Preassembled Internal Short Link assemblies with 4 poles	100
CA721/10	Preassembled Internal Short Link assemblies with 10 poles	10
CA721/100	Preassembled Internal Short Link assemblies with 100 poles	10

#### SUITABLE FOR

CTS2.5UNV0	2.5 sq.mm, 5 mm thick Feed Through Terminal Block
CTS2.5UN	2.5 sq.mm, 5 mm thick Feed Through Terminal Block