

CA624/2



connectwell
THE RIGHT CONNECTION

Pre Assembled Shorting Links

Internal Shorting Link Assemblies consist of a Current Bar shorting Sleeves and Screws. They install easily into the center of the Terminal Block and connect to the current bar. They are available as standard 2, 3, 4, 10 or 100 pole assemblies and are ready for immediate installation. Insulated pre assembled shorting link assemblies provide shock protection when installed on Terminal Blocks.

PRODUCT SPECIFICATION

| | |
|---------------|--------|
| Rated Current | 42 A |
| Torque | 0.5 Nm |

ORDERING INFORMATION

| CAT. NO. | DESCRIPTION | STD. PACK |
|----------|--|-----------|
| CA624/2 | Pre assembled Shorting Link for 2 way shorting. | 100 |
| CA624/3 | Pre assembled Shorting Link for 3 way shorting. | 100 |
| CA624/4 | Pre assembled Shorting Link for 4 way shorting. | 100 |
| CA624/10 | Pre assembled Shorting Link for 10 way shorting. | 10 |

SUITABLE FOR

| | |
|---------|--|
| CTS6USC | 6 sq.mm Spring Loaded Feed through Terminal Blocks |
| CHV6U | 6 sq.mm High Voltage Terminal Blocks. |